


IMPORTANT - READ CAREFULLY BEFORE INSTALLING FIXTURE. RETAIN THESE INSTRUCTIONS FOR FUTURE REFERENCE.
THIS PRODUCT MUST BE INSTALLED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE AND ALL APPLICABLE LOCAL CODES, BY A PERSON FAMILIAR WITH THE CONSTRUCTION AND OPERATION OF THE PRODUCT, AND THE HAZARDS INVOLVED. PROPER GROUNDING IS REQUIRED FOR SAFETY.

**NEW CONSTRUCTION PLASTER FRAME INSTALLATION (NC) - TRIM
FIXED, ADJUSTABLE OR WALL WASHER OPTIC**

- A- ENGAGE (4) HANGER BARS IN HOUSING SLOTS AVAILABLE AND CONNECT THEM TOGETHER.
B- FASTEN HANGER BARS TO CEILING JOISTS WITH #8 SCREWS (**NOT INCLUDED**). USE THE SMALL FOLDED TAB AT THE END OF THE BARS TO ALIGN WITH THE CEILING JOISTS. HANGER BARS ARE ALSO SUITABLE FOR GRID CEILING.
C- MAKE THE CUT-OUT OPENING (**SEE DIMENSIONS BELOW**).



Model	Plaster Frame	Cut-out dimension (A)	Ceiling thickness	Clearance
Laser 96	BN-LAS96RT-NC	Ø 3 3/4" (Ø 96mm)	1/8" to 1 1/2" (1 - 38mm)	6 1/2" (165mm)

